## HASSAN DISTRICT BOARD.

*Dated 23rd May 1929.*

Notice is hereby given that sealed tenders will be received at the Office of the President, District Board, Hassan, up to 2 P.M.; on Monday the 10th June 1929, for constructing a non-vegetarian kitchen with garage and Peon's quarters to the III Class T. B. at Hirisave, Channarayapatna Taluk. Approximate estimates of quantities are given below. These quantities are not guaranteed. The work should be completed by the end July 1929.

The plan, estimate and conditions may be seen at the District Board, President's Office at Hassan, between the hours of 11 A.M. and 5 P.M. on all working days.

Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Each tender must be accompanied by a deposit of Rs. 250 only in cash or Government Promissory Notes, as earnest money, and be superscribed, "Tenders for constructing a non-vegetarian kitchen with garage and peon's quarters to the III Class T. B. at Hirisave, Channarayapatna Taluk, in default of which tenders will be rejected.

The final acceptance of any tender will rest with the President, District Board, Hassan, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the President's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract for the non-vegetarian kitchen with garage to the T. B. at Hirisave, Channarayapatna Taluk.

| Details of work | Per | Rate | Quantity | Cost |
|---|---|---|---|---|
| | | | | Rs. a. p. |
| 1 Earthwork excavation foundation ... ... | C.yd. | Rs. | 40 | |
| 2 Broken jelly concrete ... ... | C.ft. | | 308 | |
| 3 Size stone in clay filling in foundation .. | ,, | | 11,295 | |
| 4 Burnt brick in clay and burnt brick in mortar at the sides. | ,, | | 1,392 | |
| 5 Burnt brick in mortar ... ... | ,, | | 349 | |
| 6 Do arch work ... ... | ,, | | 37·12 | |
| 7 Burnt stone slabs dressed 6" thick ... ... | S.ft. | | 211·50 | |
| 8 Burnt stone slabs 3 lines dressed ... ... | ,, | | 18 | |
| 9 Honne wood doors with shutters, complete ... | ,, | | 39 | |
| 10 Do windows with shutters iron bars, etc. | ,, | | 48 | |
| 11 Do ventilator with expanded iron, etc... | ,, | | 9 | |
| 12 Wall almirah with shutters and two seat planks | ,, | | 12 | |
| 13 Honne wood (wrought and put up) .. | ,, | | 75·24 | |
| 14 Roofing with first class Mangalore tiles over teak reepers. | Sqr. | | 12·33 | |
| 15 Ridge tiles set in mortar ... ... | R.ft. | | 59 | |
| 16 Ornamental teakwood pegs to walls ... | No. | | 12 | |
| 17 Ornamental teakwood finials to corners of roof small. | ,, | | 8 | |
| 18 Ornamental teakwood finials to corners of roof big. | ,, | | 4 | |
| 19 Manglore tiles flooring over 3" concrete including cement pointing. | Sqr. | | 3 48 | |
| 20 Ornamental teakwood eve board ... ... | R.ft. | | 202 | |
| 21 Mortar plastering .. ... .. | Sqr. | | 33·00 | |
| 22 Chacolate painting ... ... ... | ,, | | 3·50 | |
| 23 Chunam pointing to basement ... .. | ,, | | 3·50 | |
| 24 Earthfilling to basement ... ... ... | C.yd. | | 30 | |
| 25 Chunam borders over roof ... .. | R.ft. | | 120 | |
| 26 Cornice work to arch and gate pillars ... | ,, | | 30 | |
| 27 White and colour wash ... ... | Sqr. | | 33·00 | |
| 28 Contingencies at 5 per cent ... | ... | | ... | |

N. S. NANJUNDIAH,
*President.*